



234 W. Lincoln Avenue – Contributing (ARC Case 02-03)

Located at this address is a two-and-one-half-story cross-gabled dwelling built in the Dutch Colonial style ca. 1910. The house has a continuous ashlar-faced concrete block foundation, a gambrel and gable roof of asphalt shingles and an interior brick chimney. The first floor of this dwelling has an exterior of ashlar-faced concrete block while the second story has weatherboard siding. On the main (S) facade is an original, single-story, full-width porch enclosed ca. 1980 with weatherboard siding and six-over-six double hung wood sash windows. The recessed main entrance has a glass and wood panel door with a three-light transom. Windows in the main section of the dwelling are original, one-over-one rectangular double hung wood sash. In the gable fields are original wood shingles and the gable field on the main façade has a Palladian motif attic window. On the east façade is a ca. 1945, two-story gable addition and an original, hipped roof, single-story lateral porch with square wood columns and enclosed ca. 1945 with an exterior of weatherboard siding and an exterior wall brick chimney.

To the rear of the dwelling is an original, single-bay, frame garage with a clipped gable roof of asphalt shingles, an exterior of weatherboard siding and a ca. 1980, glass and metal garage door. Located above the door is a three-light fixed glass and wood window. – **Contributing**

